

Bid Notice and Proposal to haul, place, and roll crushed asphalt millings on N. St. Marie Road
between E. U.S. Route 50 and E. Tank Farm Lane.

Work will consist of hauling 3,500 tons of crushed asphalt millings from Richland County Stockpile at 4334 N. Meridian Road to the worksite on N. St. Marie Road. The millings will be placed on the shoulder of the road with a self-propelled road widender. The newly placed material will be rolled for compaction. The road will be broomed after shouldering to remove any loose material from the pavement. The proposed aggregate shoulder profile will be 4.5' wide with an 8% cross slope.

Contractor shall provide self-propelled road widender.

Contractor shall provide dump trucks.

Contractor shall provide roller.

Contractor shall provide power broom.

Contractor shall provide certificate of general liability insurance naming Richland County and its officers and employees as "also insured".

Contractor must abide by State of Illinois prevailing wage requirements for public construction projects.

Loading of the trucks at the stockpile will be provided by others. Flaggers and traffic control will be provided by others.

Production must be 1,600 tons per day minimum. Payment will be lump sum for the entire project. Payment will be made in full at the end of the project after an invoice has been received by Richland County.

Lump sum price to haul, spread, shape, and roll 3,200 tons of asphalt millings: \$_____

Bidders Name: _____

Bidder Address: _____

Signature of authorized agent for bidder: _____

Return sealed proposals to the Richland County Engineer at 4334 N. Meridian Road, Olney, IL 62450. Bids must be received no later than 7:00 a.m. on Thursday, November 6, 2025. At that time the bids will be publicly opened.